



SHEAR WALL SCHEDULE	
MARK	WALL
1	"LOG STACK W/ (7) 5/8" d PINS, 24" IN LENGTH, PER ROUND
2	"LOG STACK W/ (5) 5/8" d PINS, 24" IN LENGTH, PER ROUND
3	"5/8" d THRU-ROD W/ 3" d WASHER ON TOP AND 1 1/2" EMBEDDED NUTTED END ON BOTTOM
*SHEAR WALL MARK REFERS TO ALL LOGS IN LINE W/ LOG INDICATED *MIN. 2 PINS PER LOG	

ANCHOR BOLT SCHEDULE	
MARK	WALL
1	"5/8" d ANCHOR BOLT @ 24" O.C.
NOTE: ALL ANCHOR BOLT SPACING @ 36" O.C. U.N.O.	

MAIN LEVEL FLOOR PLAN
 SCALE: 1/4" = 1'-0"

1,690 SQ. FEET
 *ALL INTERIOR DOOR JAMBS ON 6" WALLS TO BE 6 1/16" UNLESS NOTED OTHERWISE
 *ALL INTERIOR DOOR JAMBS ON 4" WALLS TO BE 4 1/16" UNLESS NOTED OTHERWISE
 *ADDRESS SHALL BE INTERNALLY ILLUMINATED DURING HOURS OF DARKNESS
 *PREFAB OSBURN 2400FS WOOD STOVE APPROVAL METHOD 28 (APPROVED SPARK ARRESTORS TO BE INSTALLED ON CHIMNEY)